

Public Works Construction 2014 Budget

4th St. (E. Grand Ave to Oak St) Oak St (3rd St S to 4th St S) PROJECT SUMMARY

- **Project Length: 1,033 LF**
 - **Construction Year: 2014**
 - **Total Cost of Improvements: \$61,485 (4th)
\$186,450 (Oak)**
 - **Road Classification: Local Road**
- Project Need**

	Age (4th, Oak)	Condition
Pavement	55,46	4,2
Curb & Gutter	55,46	FAIR, VERY POOR

Pavement Condition

4th St was constructed in 1958. The pavement has reflective cracking throughout and settled areas along the curb in the parking area which are holding water and ice. The curb has cracked and heaved areas. This project adjoins Oak St., also proposed for reconstruction, and the intersection area displays additional reflective cracking. Oak St was constructed in 1967 and has severe degradation, heaving, and settlement.

Underground Utilities

	Age (4th, Oak)	Condition	Material	Proposed Work
Sanitary Sewer	85,46	FAIR	CLAY	REPLACE
Water Main	110,62	AVERAGE	CAST IRON	REPLACE
Storm Sewer	NA,46	GOOD	CONCRETE	SAVE



Curb line/roadway

Project Adoption	Date
Preliminary Resolution	05/15/2012
Public Hearing	03/05/2013
Final Resolution	03/19/2013

The existing clay sanitary and storm sewer piping on 4th St is in fair to poor condition for both grade and alignment. It is believed the sewers were constructed in 1928 as a combination sewer and was converted to sanitary only. The ductile iron water main on 4th St has exceeded its greatest expected life as it is 110 years old.

2014 Project Location Map

