

Public Works Capital Improvements

Apricot St (Broadway St to 11th St N)
 Broadway St (Franklin St to Apricot St)
 PROJECT SUMMARY

- **Project Length: 815 Ft**
- **Construction Year: 2022**
- **Total Cost of Improvements: \$ 491,000**
- **Road Classification: Local Road**




Project Need

Pavement Condition

	Install Date	Condition
Pavement	1958 (Apricot)	3
Curb & Gutter	1958 (Apricot)	3

The section of Apricot St. from 11th St. N to Broadway St. was previously constructed in 1953. And the section of Broadway St. from Apricot St. to Franklin St. was constructed in 1967. The pavement structure is at its end of life. The asphalt pavement is no longer flexible, settling and rutting are evident. The curb and gutter sections are faulting along with several areas of missing pieces of curb. Settlement of the curb and gutter has also limited draining which is accelerating the deterioration.



Underground Utilities

	Install Date	Condition	Material	Proposed Work
Sanitary Sewer	1972	Poor	8" Clay / PVC	Spot Repairs
Water Main	1982	Poor	6" Unknown	None
Storm Sewer	1970	Poor	12", 15" Clay/ PVC	Replace

Project Adoption	Date
Preliminary Resolution	1/15/2019
Final Resolution	

The sanitary sewer is 49 years old and is in poor condition with severe cracking and potential failure, and is anticipated to be replaced. The storm sewer is 51 years old and in poor condition and is anticipated to be replaced. The water main is 39 years old and is expected to be replaced during this project.

8/4/2020